

## NOTES

- LOCATE UNDERGROUND UTILITIES PRIOR TO DIGGING. CALL USA (UNDERGROUND SERVICE ALERT) 1-800-277-2600, MON THRU FRI 6AM TO 7PM, A MINIMUM 2 WORKING DAYS WITH A MAXIMUM 14 CALENDAR DAYS, TO OBTAIN A TICKET. CONTACT THE DISTRICT INSPECTOR OR PARK SUPERVISOR FOR DISTRICT UTILITIES NOT LOCATED BY USA.
- 2. EXACT LOCATION OF SIGN HOLDER TO BE AT THE DIRECTION AND APPROVAL OF THE DISTRICT REPRESENTATIVE.
- 3. CLEAR PLASTIC SHEET SHALL BE 0.06 INCH THICK CLEAR POLYCARBONATE WITH UV PROTECTION ON BOTH SIDES. "LEXAN EXELL D"; "MAKROLON SL"; "TAP PLASTICS UV2"; OR EQUAL. SHEET TO BE 15" LONG X 73/8"± WIDE TO FIT SNUGGLY INTO SLOTS AT TOP AND BOTTOM FRAMES.
- 4. PLYWOOD SHALL BE  $\frac{3}{4}$ " THICK EXTERIOR OR MARINE GRADE, A-B OR BETTER
- 5. WOOD FRAME MATERIAL SHALL BE SELECTED TO HAVE NO DEFECTS WHICH MIGHT INTERFERE WITH FABRICATION OF THE SLOTS OR INSTALLATION OF THE SCREWS. WOOD SPECIES MAY BE REDWOOD, DOUGLAS FIR, OR SIMILAR.
- 6. POSTS SHALL BE S4S NO. 1 OR NO. 2 HEART STRUCTURAL REDWOOD PER "STANDARD SPECIFICATIONS FOR GRADES OF CALIFORNIA REDWOOD LUMBER" AS PUBLISHED BY THE WESTERN WOOD PRODUCTS ASSOCIATION (WWPA).
- 7. SET POSTS PLUMB AND BACKFILL WITH NATIVE MATERIAL. REMOVE ALL ROCKS AND CLODS GREATER THAN 11/2" THEN COMPACT IN 6" LIFTS.
- 8. SCREWS SHALL BE STAINLESS STEEL #10 PHILLIPS FLAT HEAD WOOD SCREWS.
- 9. INSTALL SCREWS CENTERED ON AND PERPENDICULAR TO MEMBERS. PILOT DRILL TO PREVENT SPLITTING WOOD AS NEEDED.
- 10. PAINT WOOD SIGN HOLDER AND POST "EBRPD BROWN" PER STD PLAN 003 PAINT SPECIFICATIONS BEFORE INSTALLING CLEAR SHEET.
- 11. PRE-PRINTED INSERT SIGNS MAY BE AVAILABLE FOR PURCHASE BY PARK DISTRICT STAFF AT CENTRAL STORES.



RED LETTERS ON WHITE LARGE FONT: 3" HIGH SMALL FONT:  $\frac{9}{16}$ " HIGH

PRE-PRINTED INSERT



## **RESERVATION SIGN POST**

REVIEWED BY THE PARK STANDARDS COMMITTEE, AND APPROVED BY THE CHIEF OF DESIGN & CONSTRUCTION

2 Grigor

09/23/2022

309 SHEET 2 OF 2

STD PLAN

EAST BAY REGIONAL PARK DISTRICT - STANDARD PLANS

NOT TO SCALE