


NOT TO SCALE

EAST BAY REGIONAL PARK DISTRICT - STANDARD PLANS



## ADA ACCESSIBILITY

- 1. IF MORE THAN ONE DRINKING FOUNTAIN IS PROVIDED, AT LEAST 50% SHALL BE ACCESSIBLE
- THE CLEAR GROUND SPACE AND APPROACH DIMENSIONS SHOWN ARE THE MINIMUMS REQUIRED FOR ADA ACCESSIBLE LOCATIONS AND RECOMMENDED FOR ALL LOCATIONS.
- 3. AT ACCESSIBLE LOCATIONS, THE 8' SQUARE CONCRETE SLAB SHALL SLOPE 1.5" FROM THE HIGH EDGE TO THE LOW EDGE TO PROVIDE APPROXIMATELY 1.5% SLOPE IN THE DIRECTION OF THE GENERAL SITE DRAINAGE TO AVOID PONDING. THE CONCRETE SLAB SHALL NOT BE SLOPED TO THE DRAIN INLET WHICH IS LOCATED WITHIN THE REQUIRED ACCESSIBLE CLEAR SPACE.

## **MATERIALS**

- 4. DRINKING FOUNTAIN
  - 4.1. DRINKING FOUNTAIN MAY BE AVAILABLE AT CENTRAL STORES FOR PURCHASE BY PARK DISTRICT STAFF.
  - 4.2. MANUFACTURER: MOST DEPENDABLE FOUNTAINS, INC. (MDF) 5705 COMMANDER DR. P.O. BOX 587, ARLINGTON, TN 38002-0587, 1-800-552-6331 OR (901) 867-0039. FAX: (901) 867-0159. www.mostdependable.com
  - 4.3. MODEL: 440 SMSS EAST BAY OR 440 SMSS EAST BAY REVERSE (ADA ARM TO RIGHT), SURFACE MOUNT, STAINLESS STEEL PEDESTAL.
  - 4.4. COLOR: POWDER COAT BROWN.
  - 4.5. SURFACE CARRIER: 10NS, 10" STAINLESS STEEL INTERNAL SURFACE CARRIER.
  - 4.6. ACCESSORIES: RECESSED HOSE BIBB WITH LOCK DOOR, JUG FILLER.
  - 4.7. OPTIONAL: PET FOUNTAIN WITH SST SAND STRAINER, SST SAND STRAINERS ON HI AND/OR LOW FOUNTAINS.
- 5. CONCRETE SLAB
  - 5.1. MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 2,500 PSI.
  - 5.2. ONE POUND OF LAMPBLACK (OR 1 QUART OF LIQUID BLACK) PER CUBIC YARD OF CONCRETE, OR AS REQUIRED TO MATCH ADJACENT SITE CONCRETE.
  - 5.3. LIGHT BROOM FINISH IN SLOPE DIRECTION.
- 6. DRAIN BASIN AND GRATE. SEE PLANS.
- 7. DRAIN PIPING TO BE SOLID CORE SCHEDULE 40 PVC DWV, SOLVENT WELD.
- 8. NO-HUB DRAIN LINE COUPLING TO HAVE SST CLAMPS AND SHIELD.
- 9. WATER SUPPLY SHALL BE INSTALLED INSIDE A 1¼" PVC CONDUIT SLEEVE EXTENDING INTO VALVE BOX. SUPPLY TO BE TYPE K SOFT COPPER OR SST BRAIDED HOSE (IAPMO CERTIFIED AND NSF LISTED). FLEXIBLE SUPPLY TO BE CONTINUOUS LENGTH BETWEEN FOUNTAIN AND SHUTOFF VALVE.

## WORKMANSHIP

- 10. LOCATE UNDERGROUND UTILITIES PRIOR TO DIGGING. CALL USA (UNDERGROUND SERVICE ALERT) 1-800-277-2600, MON THRU FRI 6AM TO 7PM, A MINIMUM 2 WORKING DAYS WITH A MAXIMUM 14 CALENDAR DAYS, TO OBTAIN A TICKET. CONTACT THE DISTRICT INSPECTOR OR PARK SUPERVISOR FOR DISTRICT UTILITIES NOT LOCATED BY USA.
- 11. WRAP PIPES PASSING THROUGH SLAB WITH FOAM PIPE WRAP.
- 12. CONCRETE SLAB
  - 12.1. LIGHT BROOM FINISH IN DIRECTION OF DRAINAGE SLOPE.



DRINKING FOUNTAIN

REVIEWED BY THE PARK STANDARDS COMMITTEE, AND APPROVED BY THE CHIEF OF DESIGN & CONSTRUCTION

2 Ginga

09/23/2022

STD PLAN **515**SHEET **5** OF **5** 

EAST BAY REGIONAL PARK DISTRICT - STANDARD PLANS